

## HOW TO INSTALL AND REMOVE YOUR EVERBLOCK FLOORING

EverBlock Flooring is easy to install and remove and is designed to be transported efficiently and compactly in pre-assembled sheets, on pallets. Sections are typically stored on standard 40" x 48" pallets and transported on-site using a forklift or a truck with a lift gate. Our EverBlock transport cart may be used to efficiently transport flooring within a facility or around an event site.

### POSITIONING OF FLOORING FOR CONNECTION

EverBlock Flooring transports in pre-assembled 3ft x 3ft or 3ft x 4ft sections.



**STEP 1:** Lay first sheet so that loops are facing right and down (where you will install floor).



**STEP 2:** Position the next sheet adjacent to the first, with the male clips facing the female loops, ready to be snapped in place.




**STEP 3:** Use your foot to nudge flooring over to the first panel, such that the male clips ride onto the female loops. Sections are designed to self-align when nudged together.



**STEP 4:** Use a backwards kick with your heel to engage the male clip into the female loop. Kick backwards towards the loop and over the clip.

### DISMANTLING YOUR FLOOR

### FOLDING METHOD




STEP 1




STEP 2



STEP 3



STEP 4



STEP 5



STEP 6

### DISMANTLING YOUR FLOOR

### ZIPPER METHOD



STEP 1



STEP 2



STEP 3



STEP 4



STEP 5



STEP 6



STEP 7



STEP 8



STEP 9

In general, we recommend working in complete rows, such that the entire row of sheets is disengaged first and then the row itself is broken down into sheets using the same tip and disconnect method. **DO NOT** pull straight up on tiles when they are flat as this has the potential to damage the connection system. Sections are designed to disconnect when tipped, which is always the preferred method of dismantling your floor. On a larger scale installation, you may find yourself disconnecting a row of sheets such that part is tipping while the rest of the row remains on the floor. Move slowly along the line, disconnecting sections as you go such that at the end the entire row is disengaged and ready to be broken down further into sheets. **Note:** We recommend cleaning floor sections prior to dismantling and storing, as it is easiest to clean a floor when its laid out.